BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name of work: construction of culverts and Improvements of Drains at Dasarahalli Surrounding area in ward No. 06 Byatarayanapura Sub Division

			Estimate Cost Rs.						2000000.00
Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 143/ Item No. 19.1/ PWD SR 2018-19	Cum							
	Culverts		19	6.20	2.10	1.20	296.86		
							296.86	137.80	**40907.00**
	Basic Rate	130.00							
	Area Weightage @ 6%	7.80							
	Total	**137.80**							
2	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 13/ Item No. 4.3/ PWD SR 2018-19	**Cum**							
	For Culverts		19	6.20	2.10	0.15	38.17		
							38.17	5408.12	**206433.00**
	Basic Rate	5102.00							
	Area Weightage @ 6%	306.12							
	Total	**5408.12**							
3	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 25/ Item No. 5.6/ PWD SR 2018-19	cum							
	Culverts		19X2	6.20	0.60	0.50	70.68		
							70.68	4871.76	**344336.00**
	Basic Rate	4596.00							
	Area Weightage @ 6%	275.76							
	Total	**4871.76**							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
4	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 25/ Item No. 5.9/ PWD SR 2018-19	Sqm							
	Culverts		19X2	6.20	0.50	0.45	53.01		
							53.01	**5811.98**	**308093.00**
	Basic Rate	5483.00							
	Area Weightage @ 6%	328.98							
	Total	**5811.98**							
5	KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 17/ Item No. 4.34/ PWD SR 2018-19	Sqm							
	For Culverts		19	6.20	0.60		70.68		
	For Sides		19X2	6.20	0.23		54.19		
			19X2	1.65	0.23		14.42		
							139.29	**309.52**	**43113.00**
	Basic Rate	**292.00**							
	Area Weightage @ 6%	17.52							
	Total	**309.52**							
6	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2018-19	cum							
	Culverts		19X2	6.20	0.50	0.15	17.67		
	Vent Bed		19	6.20	0.60	0.15	10.60		
							28.27	5627.54	**185839.00**
	Basic Rate	5309.00							
	Area Weightage @ 6%	318.54							
	Total	**5627.54**							
7	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 115/ Item No. 15.1/ PWD SR 2018-19	Sqm							
	Culverts		19X2	6.20		0.50	117.80		

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
							117.80	223.66	**26347.00**
	Basic Rate	211.00							
	Area Weightage @ 6%	12.66							
	Total	**223.66**							
8	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 14/ Item No. 4.11/ PWD SR 2018-19	**Cum**							
	For Cuvlerts		19	6.20	1.80	0.23	48.77		
							48.77	5998.54	**292544.00**
	Basic Rate	5659.00							
	Area Weightage @ 6%	339.54							
	Total	**5998.54**							
9	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 18/ Item No. 4.46.2/ PWD SR 2018-19	**Qtl**							
	0.82Ton/Cum		0.082	48.77			**4.00**	75223.96	**300826.00**
	Basic Rate	70966.00							
	Area Weightage @ 6%	4257.96							
	Total	**75223.96**							
10	KSRRB M100-2. Loading and Unloading of stone boulders by manual means complete as per specification MORTH-100/chapter-1 Page No. 136/ Item No. 17.1/ PWD SR 2018-19	Cum							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
			Qty. Vide Item No. 1+2				296.86		
							296.86	60.42	17936.00
	Basic Rate	57.00							
	Area Weightage @ 6%	3.42							
	Total	60.42							
							Grand Total		1766374.00
11	For 12% Applicable GST								211965.00
12	For 1% Third Party Inspection charges								17664.00
13	Miscesallaneous Charges	L/S							3997.00
									2000000.00

Certificate:

1. The work spot has been inspected and the work is found necessary.
2. This estimate is prepared as per PWD SR of 2018-19
3. The provisions were made in this estimate are necessary and adequate.
4. This works come under B.B.M.P. limits.

Assistant Engineer
Ward No. 86(Thanisandra)

Executive Engineer
Bruhat Bangalore Mahanagara Palike
Byatarayanapura Division

Assistant Executive Engineer
Bruhat Bangalore Mahanagara Palike
Byatarayanapura Sub Division

Administrative Approval

Accorded For Rs 20.00 Lakhs
Head of A/C P-1771
CER NO : 16 Dt: 09-05-2019

TA CE (YNK)

TECHNICAL SANCTION

Accorded For Rs 20.00 Lakhs
Head of A/C P-1771, POW Level.
Div. Ref. No. 15/19-20 Date 09/05/19

AEE 9/05 EE(BTP)